

TABLE OF CONTENTS

- A. Construction Requirements
- B. Class 2 Penetrating Concrete Sealer
- C. Rapid Set Concrete Patching Material – Vertical and Overhead Repairs
- D. Rapid Set Concrete Patching Material – Horizontal Repairs
- E. Clean and Epoxy Seal
- F. Surface Sealing Concrete
- G. Removal of Cathodic Protection System
- H. Surface Sealing Low Slump Concrete
- I. Removal of Existing Bearings
- J. Epoxy Pressure Injecting
- K. Cleaning and Coating Existing Bearings
- L. Curing Concrete Adjacent to Expansion Device

<p>“THIS MEDIA SHOULD NOT BE CONSIDERED A CERTIFIED DOCUMENT.”</p>	<p>MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION 105 W. CAPITOL AVE. JEFFERSON CITY, MO 65101 Phone (888) 275-6636</p>
	<p>If a seal is present on this sheet, JSP's has been electronically sealed and dated.</p>
	<p>JOB NO. J4I2381 Clay County, MO Date Prepared: 12/19/2012</p>

JOB SPECIAL PROVISIONS (BRIDGE)

A. CONSTRUCTION REQUIREMENTS

1.0 Description. This provision contains general construction requirements for this project.

2.0 Construction Requirements. Plans for the existing structure(s) are included in the contract with the bridge plans for informational purposes only.

2.1 In order to assure the least traffic interference, the work shall be scheduled so that a lane closure is for the absolute minimum amount of time required to complete the work. A lane shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed lane is opened to traffic.

2.2 Qualified special mortar shall be a qualified rapid set concrete patching material in accordance with [Sec 704](#). A qualified rapid set concrete patching material will not be permitted for repairing concrete deck (half-soling), deck repair with void tube replacement, full depth repair, modified deck repair and substructure repair (formed) unless a note on the bridge plans specifies that a qualified special mortar may be used.

2.3 Provisions shall be made to prevent any debris and materials from falling into the stream, lake or onto the roadway. Any debris and materials that falls below the bridge outside the limits mentioned previously and if determined necessary by the engineer, the debris shall be removed as approved by the engineer at the contractor's expense. Traffic under the bridge shall be maintained in accordance with the contract documents.

2.4 Any damage sustained to the remaining structure as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.

2.5 In rehabilitating Br. No. A15802, the proposed Int. Bt. No. 5A shall be constructed as near to completion as feasible before closing the structure to traffic. The new bent shall be completed and the adjacent hinge bearings removed before starting any deck rehabilitation work above that would be affected by the lifting operation. With the end of the slab supported by the new bent, the existing roadway grade above shall remain unchanged.

2.6 Provisions shall be made to prevent damage to any existing utilities. Any damage sustained to the utilities as a result of the contractor's operations shall be the responsibility of the contractor. All costs of repair and disruption of service shall be as determined by the utility owners and as approved by the engineer.

3.0 Coating Information.

3.1 Straps Removal. Exposed portions of straps for stay-in-place forms shall be removed prior to surface preparation. Straps need not be removed in areas that are not being painted. Flame cutting will not be permitted. The contractor shall exercise care not to damage the existing structure during removal. Any damage sustained to the remaining structure as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.

3.2 Slab Drains and Stay-In-Place Forms. The stay-in-place forms, the slab drains and slab drain brackets shall not be recoated or overcoated or damaged during the painting operation. Any portion of the slab drain bracket that is blast cleaned shall be recoated with System G. Any

JOB SPECIAL PROVISIONS (BRIDGE)

damage sustained as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.

3.3 Existing Bridge Information. The informational plans may be used by bidders in determining the amount of steel to be cleaned and painted/coated with the full understanding that the State accepts no responsibility for accuracy of the estimated tons of existing steel shown in the table below. The bidder's acceptance and use of the estimate shown below shall be no cause for claim for any final adjustment in the contract unit price for the work involved in repainting. Each bidder is expected to carefully examine the structure(s), investigate the condition of existing paint and to prepare their own estimate of quantities involved before submitting a bid. Surface preparation and applying field coatings to the structural steel will be based on the contract plan quantities. No final measurements will be made.

Bridge No.	Estimated Tons			Existing Paint System	Lead Based
	Coating System		Total		
	System G	Calcium Sulfonate			
A33741	9	0	9	B ('83)	Yes
A33751	35	0	35	B ('83)	Yes
A33771	5	0	5	B ('82)	Yes
A33781	4	0	4	B ('82)	Yes
A33861	3	0	3	B ('83)	Yes
A33881	14	0	14	B ('83)	Yes

3.4 Environmental Contact. Environmental Section may be contacted at the below address or phone number. The Missouri Department of Health may be contacted at 573-751-6102.

- (a) MoDOT - Design Division - Environmental Section
 PO Box 270
 105 W Capitol Ave, Jefferson City, MO 65102
 Telephone (573) 526-4778

3.5 Approved Smelters and Hazardous Waste Treatment, Storage and Disposal Facilities. The following are the approved smelters and hazardous waste treatment, storage and disposal facilities:

- (a) Doe Run Company-Resource Recycling Division-Buick Facility
 Highway KK
 Boss, MO 65440
 Telephone 573-626-4813
- (b) Doe Run Company-Herculaneum Smelter
 881 Main Street
 Herculaneum, MO 63048
 Telephone 314-993-3164

4.0 Method of Measurement. No measurement will be made.

5.0 Basis of Payment. Payment for the above described work will be considered completely covered by the contract unit price for other items included in the contract.

JOB SPECIAL PROVISIONS (BRIDGE)

B. CLASS 2 PENETRATING CONCRETE SEALER

1.0 Description. This work shall consist of preparing and treating the concrete bridge deck, approach slabs, roadway face and top of barrier curb surfaces with a class 2 penetrating concrete sealer meeting this specification. This type of sealer shall be used in lieu of the normal surface sealing for concrete in accordance with Sec 703.

2.0 Materials. The sealer shall meet the requirements of this job special provision. The sealer selected by the contractor shall be submitted to the engineer for approval two weeks before application and shall be listed on MoDOT's Pre-Qualified Product List. If the contractor chooses to submit a new product for MoDOT's Pre-Qualified Product List, the product shall be submitted to the engineer 30 days prior to application. Either submittal shall include certified test data from an independent test laboratory and the concrete mix design and curing procedure on the test specimens in which sealer was tested.

2.1 The sealer shall be a solvent-free 100% solids isobutyltrialkoxysilane, with low oligomer and polymer compound content. The chemical composition shall meet the following requirements:

Property	Specification
Purity	98% minimum monomer by weight
Solvent	Less than 0.1% by weight
Siloxan or polymer Residue	Less than 0.1% by weight
Chloride Ion Content	Less than 40 PPM
Density	ASTM D2111: 7.2 to 7.4 pounds per gallon
Flash Point	ASTM D93: greater than 145 degrees F
Dry Time	ASTM D7539: less than one hour

2.2 The sealer shall meet the following performance criteria based on a single application at the manufacturer's recommended application rate. All test specimens shall be produced using MoDOT Class B-2 concrete in accordance with Section 501.

Test	Test Method	Duration	Max Absorption / Cl ⁻
Water Immersion	ASTM C 642	48 hours	0.5 percent by weight (mass)
Water Immersion	ASTM C 642	50 days	1.5 percent by weight (mass)
Salt Water Ponding (based on non-abraded specimen)	AASHTO T 259	90 days	0.50 lbs/cu yd (0.30 kg/m ³) Cl ⁻ Depth: (1/2 to 1") (13 to 25 mm)

2.2.1 Absorption. The absorption of the treated concrete under total immersion shall not exceed 0.5 percent after 48 hours or 1.5 percent after 50 days per ASTM C 642 as modified below for non-air entrained concrete.

2.2.1.1 In addition to ASTM C 642 section 4.1, one 4-inch (10 cm) diameter by 4 inch (10 cm) long core shall be retrieved from the surface of a concrete test specimen to which sealer has been applied. No coring are to be taken from the bridge deck. The core shall be oven dried as designated by ASTM C 642 section 5.1. The core shall be sealed with a rapid setting two part epoxy on the sides and bottom. The epoxy shall overlap the top edge of the core 1/8" (3mm). The core shall be weighed to determine the oven dry weight (mass) of the core and coating. The weight (mass) shall be designated as "A".

2.2.1.2 The core, processed in accordance with section 2.2.1.1 of this job special provision, shall be immersed in a suitable receptacle and covered with tap water. The procedure as

JOB SPECIAL PROVISIONS (BRIDGE)

designated by ASTM C 642 section 5.2 shall be followed to determine the soaked surface dry weight (mass) of the core and coating. This weight (mass) shall be designated as "B".

2.2.1.3 The percent moisture absorption of the core shall be determined by ASTM C 642 section 6.1, equation (1). ASTM C 642 sections 5.3, 5.4, 6.1 and equations (2) through (7) shall not apply.

2.2.2 Salt water ponding. After 90 days ponding of 3 percent NaCl solution per ASSHTO T 259, the chloride ion content of the concrete shall not exceed 0.5 pounds per cubic yard (0.30 kg/m³) at ½ to 1 inch (13 to 25 mm) depth.

2.3 The sealer shall not permanently stain, discolor or darken the concrete. Application of the sealer shall not alter the surface texture or form a coating on the concrete surfaces. Treated concrete shall be surface dry within 60 minutes after application.

2.4 The sealer shall be tinted with a fugitive dye to enable the coating to be visible on the treated concrete surface for at least 4 hours after application. The fugitive dye shall not be conspicuous more than 7 days after application when exposed to direct sunlight.

2.5 The sealer shall be delivered to the project in unopened containers with the manufacturer's label identifying the product and with the seal(s) intact. Each container shall be clearly marked by the manufacturer with the following information:

- Manufacturer's name and address.
- Product name.
- Date of manufacture and expiration date.
- Lot identification.
- Storage requirements.

3.0 Construction Requirements.

3.1 Equipment. Application equipment shall be as recommended by the manufacturer. The spray equipment, tanks, hoses, brooms, rollers, coaters, squeegees, etc. shall be thoroughly clean, dry, free of foreign matter, oil residue and water prior to applying the treatment.

3.2 Cleaning and Surface Preparation. Surfaces which are to be treated shall meet the approved product's requirements for surface condition. Sealing shall not be done until all concrete construction or repair has been completed and cured to the requirements of the manufacturer. A minimum of a 7 day wet cure and 5 day drying period are required. The contractor shall furnish the engineer with written instructions for the surface preparation requirements and a representative of the manufacturer shall be present to assure that the surface conditions meet the manufacturer's requirements.

3.2.1 Sealing shall be done after the bridge deck has been textured.

3.2.2 At a minimum, the surface shall be thoroughly cleaned to remove dust, dirt, oil, wax, curing components, efflorescence, laitance, coatings and other foreign materials. The manufacturer or manufacturer's representative shall approve the use of chemicals and other cleaning compounds to facilitate the removal of these foreign materials before use. The treatment shall be applied within 48 hours following surface preparation.

JOB SPECIAL PROVISIONS (BRIDGE)

3.2.3 Cleaning equipment shall be fitted with suitable traps, filters, drip pans and other devices to prevent oil and other foreign material from being deposited on the surface.

3.3 Test Application. Prior to final application, the contractor shall treat a measured test coverage area on horizontal and vertical surfaces of the different components of the structure to be treated for the purpose of demonstrating the desired physical and visual effect on an application or of obtaining a visual illustration of the absorption necessary to achieve the specified coverage rate. In the latter case, the applicator shall use at least ½ gallon (1.9 liter) of treatment following the manufacturer's recommended method of application for the total of the test surfaces. Horizontal test surfaces shall be located on the deck and on the curb or sidewalk, and vertical test surfaces shall be located on a parapet or safety barrier curb so that the different textures are displayed.

3.4 Application. The sealer shall be applied by thoroughly saturating the concrete surfaces at an application rate of 175 square feet per gallon or the rate designated on the plans.

3.4.1 The concrete surface temperature shall be above 35°F (2°C).

3.4.2 Allow concrete to dry a minimum of 48 hours after any measurable precipitation.

3.4.2 The treatment shall be spread from puddles to dry areas.

3.4.3 If the applicator is unable to complete the entire application continuously, the location where the application was stopped shall be noted and clearly marked.

3.5 Protection of Adjoining Surfaces and the Public.

3.5.1 When applying the sealer, the contractor shall protect adjoining surfaces of the structure that are not to be sealed by masking off or by other means. Sealer shall not leave residue on glass, painted metal or automobiles. The contractor shall also make provision to protect the public when sealing the fascia of a bridge that spans an area used by the public.

3.5.2 Asphalt and mastic type surfaces shall be protected from spillage and heavy overspray. Joint sealants, traffic paints and asphalt overlays may be applied to the treated surfaces 48 hours after the treatment has been applied. Adjoining and nearby surfaces of aluminum or glass shall be covered where there is possibility of the treatment being deposited on the surfaces. Plants and vegetation shall be protected from overspray by covering with drop cloths. Precautions shall be followed as indicated on the manufacturer's product and material safety data sheet.

3.6 Opening to Traffic. Traffic shall be allowed on a deck only after a treated area is visibly dry. Dried coating shall not leave residue on glass, painted metal or automobiles.

4.0 Method of Measurement. No direct measurement will be made.

5.0 Basis of Payment. Payment for the above described work shall be considered completely covered by the contract unit price for other items included in the contract.

C. RAPID SET CONCRETE PATCHING MATERIAL – VERTICAL AND OVERHEAD REPAIRS JSP-02-01

1.0 Description. This specification covers cementitious concrete, polymer-modified concrete and polymer concrete that are suitable for repairing concrete surfaces on bridges or concrete structures, particularly under fast setting or special conditions. The repairs would involve vertical or overhead applications. The work shall consist of removing, furnishing, preparing, and placing materials at locations as shown on the plans or as directed by the engineer.

2.0 Material. All materials shall be in accordance with MoDOT specifications and as noted herein.

2.1 Aggregate For Extending Commercial Mixture. Coarse and fine aggregates shall be in accordance with [Sec 1005](#), except the requirements for gradation and percent passing the No. 200 sieve shall not apply. Coarse aggregate meeting Gradation E requirements shall be used for repairs greater than one inch (25 mm) in depth. Fine aggregate will be allowed for repairs less than one inch (25 mm). Aggregate specified, bagged, labeled and furnished by the rapid set concrete patching material manufacturer may also be used for mortar extension.

2.2 Material Applications. The contractor shall select and use the product most suitable for the work and field conditions in accordance with these specifications.

2.3 Curing. Rapid set concrete patching material shall be cured until the minimum compressive strength 1500 psi is attained using standard curing specifications, unless otherwise specified by the manufacturer.

2.4 Qualification and Project Acceptance.

2.4.1 Inspection. All materials shall be subject to inspection and sampling by MoDOT at the source of manufacture, intermediate shipping terminal or destination. MoDOT will be allowed free access to all facilities and records as required to conduct inspection and sampling.

2.4.2 Qualification. Prior to use, rapid set concrete patching materials need to be qualified.

2.4.2.1 Requested Information. The manufacturer shall submit with samples of the materials, a written request to Construction and Materials with the following information:

- (a) New Products Evaluation Form
- (b) Brand name of the product.
- (c) Certification that the material meets this specification.
- (d) Certified test results from an independent laboratory showing compliance with this specification.
- (e) Specific preparation instructions of repair area.
- (f) Specific mixing, handling and curing instructions.
- (g) Application type (i.e., vertical or overhead).

JOB SPECIAL PROVISIONS (BRIDGE)

2.4.2.2 Field Evaluation. Final approval will be granted when the following requirements are met:

- (a) MoDOT report documenting two years of field performance on MoDOT system. The report will contain the placement date, field observations (semi annual), description of field performance and photographs of in-place material.
- (b) A manufacturer's representative shall be present during placement of the material to provide technical expertise.

2.4.2.2.3 Disqualification. If during the two year observation period the repair area(s) fails the product will not be added to the qualified list.

2.5 Qualified List. The listing of qualified products are available from Construction and Materials or on MoDOT's web site. New certified test results and samples shall be submitted any time the manufacturing process or the material formulation is changed. The material will be subject to removal from the qualified list if there is evidence of unsatisfactory performance or a change in manufacturing process or formulation, or when random sampling and testing of material offered for use indicates nonconformity with any of the requirements herein specified.

2.6 Certification. The contractor shall supply a manufacturer's certification to the engineer for each lot of material furnished. The certification shall include the name of the manufacturer, a manufacturer certification statement that the material supplied is the same as that qualified and listing the date of qualification.

2.7 Acceptance. Acceptance of the material will be based on the use of a qualified product, the manufacturer's certification that the material supplied is the same as that approved and upon the results of such tests as may be performed by the engineer.

3.0 Mixture. Unless otherwise specified, rapid set concrete patching material shall be approved commercial mixtures meeting [Sections 3.1 – 3.1.3.](#) Rapid set concrete patching materials shall be specifically designed for the application needed.

3.1 Commercial Mixtures. Rapid set concrete patching material in its sacked form and mixtures when properly prepared in accordance with the manufacturer's specifications, shall meet the minimum test requirements given in Table 1. Mixtures may be supplied, as required, as a patching mortar or as a patching mortar with aggregate extension. If the material is to be supplied with extender aggregate, this shall also pass the required tests in Table 1 using the maximum allowed amount of extender aggregate.

3.1.1 Mixture Requirements. Rapid set concrete patching material shall be single packaged dry mix requiring the addition of water or other liquid component just prior to mixing. The material shall not contain soluble chlorides as an ingredient of manufacture. The material shall be placed in accordance to the manufacturer's recommendations.

JOB SPECIAL PROVISIONS (BRIDGE)

Table 1 (English Unit)				
Physical Test Property	Specification	Requirement for cementitious concrete	Requirement for polymer-modified concrete	Requirement for polymer concrete
Bond Strength by Slant Shear	ASTM C882/C928 ²	min. 1000 psi @ 24hrs.& min. 1500 psi @ 7 days	n/a	min. 1000 psi @ 24hrs.& min. 1500 psi @ 7 days
Linear Coefficient of Thermal Expansion ¹ (for bagged mortar only, without extension aggregate)	ASTM C531	n/a	n/a	4 – 8 X 10-6 in/in/deg F
Resistance to Rapid Freezing & Thawing	AASHTO T161 or ASTM C666	80% min. using Procedure B ³ (300 Cycles)	80% min. using Procedure B ³ (300 Cycles)	n/a
Compressive Strength	AASHTO T22 or ASTM C39	1500 psi @ 3 hr & 3000 psi @ 24 hr	1500 psi @ 3 hr & 3000 psi @ 24 hr	n/a
Rapid Chloride Permeability	AASHTO T277 or ASTM C1202	1000 coulombs @ 28 days	1000 coulombs @ 28 days	1000 coulombs @ 28 days
Length Change	AASHTO T 160 or ASTM C157	In water Storage (+0.15) In air storage (-0.15)	In water storage (+0.15) In air storage (-0.15)	n/a
Color		gray	gray	gray

¹ Not required for extended mixtures if the mortar passes this requirement.

² ASTM C882 shall be performed on non-water based materials. ASTM C928 shall be performed on water-based materials.

³ Procedure A may be used in lieu of Procedure B

3.1.2 Construction Requirements. The manufacturer shall provide with the bagged mixture, specifications for the mixing procedure, amount and kind of liquid to be added, and the amount of aggregate extension allowed, if any. All mixing, handling and curing practices recommended by the manufacturer shall be followed and will be considered a part of these specifications.

3.1.3 Removal from Qualified List. All mixtures shall be approved before use. Reoccurring failures of any mixture for any reason will be cause for removal from the qualified list.

3.2 Vertical Repair.. A qualified rapid set concrete patching material approved for vertical use may be used when specified on the plans and as approved by the engineer. The engineer will make field cylinders to verify the 1500 psi (10 MPa) minimum strength. The material shall adhere to the concrete surface without sagging.

3.3 Overhead Repair. A qualified rapid set concrete patching material approved for overhead use may be used when specified on the plans and as approved by the engineer. The material shall be placeable in layers of at least 1 inch on overhead applications without the use of formwork or anchoring devices. The material shall adhere to the concrete surface without sagging. The engineer will make field cylinders to verify the 1500 psi (10 MPa) minimum strength.

4.0 Construction Requirements.

4.1 Mixing. Rapid set concrete patching material shall be mixed and finished according to the manufacturer's recommendation.

4.2 Preparation of Repair Area. Deteriorated, damaged or defective concrete as shown on the plans, required by the specifications or as directed by the engineer, shall be removed. All exposed reinforcement shall be thoroughly cleaned as shown on the plans, required by the specifications or as directed by the engineer. Unless otherwise specified by the commercial mixture manufacturer, the existing surface shall be damp and all free water shall be removed prior to placement of the required material.

4.3 Bonding Agent. A bonding agent may be used if recommended by the rapid set concrete patching material manufacturer.

5.0 Method of Measurement. No measurement will be made for rapid set concrete patching material.

6.0 Basis of Payment. Rapid set concrete patching material will be paid for at the contract unit price for other items and will be considered full compensation for all labor, equipment and material to complete the described work.

D. RAPID SET CONCRETE PATCHING MATERIAL – HORIZONTAL REPAIRS JSP-02-01A

1.0 Description. This specification covers cementitious concrete, polymer-modified concrete and polymer concrete that are suitable for repairing concrete surfaces on bridges or roadways, particularly under fast setting or special conditions. The repairs would involve horizontal applications. The work shall consist of removing, furnishing, preparing, and placing materials at locations as shown on the plans or as directed by the engineer.

2.0 Material. All materials shall be in accordance with MoDOT specifications and as noted herein.

2.1 Aggregate For Extending Commercial Mixture. Coarse and fine aggregates shall be in accordance with [Sec 1005](#), except the requirements for gradation and percent passing the No. 200 sieve shall not apply. Coarse aggregate meeting Gradation E requirements shall be used for repairs greater than one inch (25 mm) in depth. Fine aggregate will be allowed for repairs less than one inch (25 mm). Aggregate specified, bagged, labeled and furnished by the rapid set concrete patching material manufacturer may also be used for mortar extension.

2.2 Material Applications. The contractor shall select and use the product most suitable for the work and field conditions in accordance with these specifications.

2.3 Curing. Rapid set concrete patching material shall be cured until the minimum compressive strength 3200 psi is attained using standard curing specifications, unless otherwise specified by the manufacturer.

2.4 Qualification and Project Acceptance.

2.4.1 Inspection. All materials shall be subject to inspection and sampling by MoDOT at the source of manufacture, intermediate shipping terminal or destination. MoDOT will be allowed free access to all facilities and records as required to conduct inspection and sampling.

2.4.2 Qualification. Prior to use, rapid set concrete patching material shall be qualified. In order to become qualified, a material shall have completed testing through AASHTO's National Transportation Product Evaluation Program (NTPEP). The manufacturer shall contact the AASHTO/NTPEP coordinator to obtain the testing location for the rapid setting concrete patching material.

2.4.2.1 Requested Information. The manufacturer shall submit with samples of the materials, a written request to Construction and Materials with the following information:

- (a) Brand name of the product.
- (b) Certification that the material meets this specification.
- (c) NTPEP test results showing compliance with this special provision.
- (d) Specific mixing, handling and curing instructions.
- (e) Application type (i.e., bridge or roadway).

2.4.2.2 Qualified List. Upon approval by the engineer, the brand name and manufacturer will be placed on a qualified list of rapid set concrete patching materials. The listing of qualified materials is available from Construction and Materials or on MoDOT's web site. New certified test results and samples shall be submitted any time the manufacturing process or the material formulation is changed. The material will be subject to removal from the qualified list if there is evidence of unsatisfactory performance or a change in manufacturing process or formulation, or when random sampling and testing of material offered for use indicates nonconformity with any of the requirements herein specified.

2.4.3 Provisional Approval. Provisional approval may be granted provided the following requirements have been met:

- (c) New Products Evaluation Form
- (d) Certified test results from an independent laboratory showing compliance with this special provision.
- (e) Documentation prepared by MoDOT covering two years of field performance on MoDOT's system. MoDOT will need to approve the location of the test site. Documentation will contain the placement date, field observations (semi-annual), description of field performance and photographs of in-place material.
- (f) During placement the manufacturer's representative shall be present on the project to provide technical expertise.

JOB SPECIAL PROVISIONS (BRIDGE)

2.4.3.1 Disqualification. If during the two year observation period the repair area(s) fails provisional approval will not be granted. Repair area(s) experiencing any cracking, debonding or spalling will be considered a failure.

2.4.3.2 Length of Provisional Approval. Provisional approval will be granted for three years or until NTPEP testing is completed.

2.5 Certification. The contractor shall supply a manufacturer's certification to the engineer for each lot of material furnished. The certification shall include the name of the manufacturer, a manufacturer certification statement that the material supplied is the same as that qualified and listing the date of qualification.

2.6 Acceptance. Acceptance of the material will be based on the use of a qualified or provisionally approved material, the manufacturer's certification that the material supplied is the same as that approved and upon the results of such tests as may be performed by the engineer.

3.0 Mixture. Unless otherwise specified, rapid set concrete patching material shall be approved commercial mixtures meeting [Sections 3.1 – 3.1.3](#) or deck repair cementitious mortar meeting [Section 3.2](#). Rapid set concrete patching materials shall be specifically designed for the application needed.

3.1 Commercial Mixtures. Rapid set concrete patching material in its sacked form and mixtures when properly prepared in accordance with the manufacturer's specifications, shall meet the minimum test requirements given in Table 1. Mixtures may be supplied, as required, as a patching mortar or as a patching mortar with aggregate extension. If the material is to be supplied with extender aggregate, this shall also pass the required tests in Table 1 using the maximum allowed amount of extender aggregate.

3.1.1 Mixture Requirements. Rapid set concrete patching material shall be single packaged dry mix requiring the addition of water or other liquid component just prior to mixing. The material shall be capable of ½ inch (13 mm) to full depth repair and require no bonding agent. The material shall not contain soluble chlorides as an ingredient of manufacture. The material shall be placed in accordance to the manufacturer's recommendations.

Table 1 (English Unit)				
Physical Test Property	Specification	Requirement for cementitious concrete	Requirement for polymer-modified concrete	Requirement for polymer concrete
Bond Strength by Slant Shear ¹	ASTM C882/C928 ³	min. 1000 psi @ 24hrs.& min. 1500 psi @ 7 days	n/a	min. 1000 psi @ 24hrs.& min. 1500 psi @ 7 days
Linear Coefficient of Thermal Expansion ^{1, 2} (for bagged mortar only, without extension aggregate)	ASTM C531	n/a	n/a	4 – 8 X 10-6 in/in/deg F
Resistance to Rapid Freezing & Thawing ¹	AASHTO T161 or ASTM C666	80% min. using Procedure B ⁵ (300 Cycles)	80% min. using Procedure B ⁵ (300 Cycles)	n/a

JOB SPECIAL PROVISIONS (BRIDGE)

Table 1 (English Unit)				
Physical Test Property	Specification	Requirement for cementitious concrete	Requirement for polymer-modified concrete	Requirement for polymer concrete
Compressive Strength ¹	AASHTO T22 or ASTM C39	3200 psi @ 3 hr & 4000 psi @ 7 days	3200 psi @ 3 hr & 4000 psi @ 7 days	n/a
Rapid Chloride Permeability ¹	AASHTO T277 or ASTM C1202	<u>Bridge Decks</u> 1000 coulombs @ 28 days <u>Roadway</u> 2000 coulombs @ 28 days	<u>Bridge Deck</u> 1000 coulombs @ 28 days <u>Roadway</u> 2000 coulombs @ 28 days	<u>Bridge Deck</u> 1000 coulombs @ 28 days <u>Roadway</u> 2000 coulombs @ 28 days
Length Change ^{1, 4}	AASHTO T 160 or ASTM C157	In water Storage (+0.15) In air storage (-0.15)	In water storage (+0.15) In air storage (-0.15)	n/a
Color		gray	gray	gray

¹The commercial mix test values can be located in the AASHTO's National Transportation Product Evaluation Program (NTPEP) reports for Laboratory Evaluations of Rapid Set Concrete Patching Materials. Data for provisionally approved materials is located at the Construction and Materials Division.

²Not required for extended mixtures if the mortar passes this requirement.

³ ASTM C882 shall be performed on non-water based materials. ASTM C928 shall be performed on water-based materials.

⁴ As modified by ASTM C928.

⁵ Procedure A may be used in lieu of Procedure B

3.1.2 Construction Requirements. The manufacturer shall provide with the bagged mixture, specifications for the mixing procedure, amount and kind of liquid to be added, and the amount of aggregate extension allowed, if any. All mixing, handling and curing practices recommended by the manufacturer shall be followed and will be considered a part of these specifications.

3.1.3 Removal from Qualified List. All mixtures shall be approved before use. Reoccurring failures of any mixture for any reason will be cause for removal from the qualified list.

3.2 Deck Repair Concrete. A qualified rapid set concrete patching material indicated for horizontal use and intended for patching concrete bridge decks may be used when specified on the plans and as approved by the engineer. If this option is selected, the contractor shall provide a trial mix to determine the total cure time needed to achieve a compressive strength of 3200 psi (22 MPa). Compressive specimens shall be prepared in accordance with current MoDOT test methods and cured to simulate actual field conditions. Testing of compressive specimens shall be performed by methods and at facilities acceptable to the engineer. The repaired deck shall not be opened to traffic until at least 4 hours after the last placement of deck repair concrete, the established cure time has elapsed and until such concrete has achieved a compressive strength of 3200 psi (22 MPa). A new trial mix may be required if the engineer determines the field conditions vary substantially from trial mix conditions. The engineer will make field cylinders to verify the 3200 psi (22 MPa) minimum strength.

4.0 Construction Requirements.

4.1 Mixing. Rapid set concrete patching material shall be mixed and finished according to the manufacturer's recommendation.

4.2 Preparation of Repair Area. Deteriorated, damaged or defective concrete as shown on the plans, required by the specifications or as directed by the engineer, shall be removed. All exposed reinforcement shall be thoroughly cleaned as shown on the plans, required by the specifications or as directed by the engineer. Unless otherwise specified by the commercial mixture manufacturer, the existing surface shall be damp and all free water shall be removed prior to placement of the required material.

4.3 Bonding Agent. A bonding agent may be used if recommended by the rapid set concrete patching material manufacturer.

5.0 Method of Measurement. No measurement will be made for rapid set concrete patching material.

6.0 Basis of Payment. Rapid set concrete patching material will be paid for at the contract unit price for other items and will be considered full compensation for all labor, equipment and material to complete the described work.

E. CLEAN AND EPOXY SEAL

1.0 Description. In order to protect the bridge superstructure concrete from deicing chemicals and other contaminants, loose and delaminated concrete shall be removed and an epoxy seal shall be applied to the concrete in the area of curb outlets and the vertical face of the curbs in accordance with the bridge plans and this job special provision.

2.0 Construction Requirements. All loose and delaminated concrete in the areas as required by this job special provision shall be removed in the cleaning process with hand tools. Hand tools may include chipping chisels, wire brushes, dust brushes, etc. After the loose and delaminated concrete has been removed to the satisfaction of the engineer, the epoxy sealing preparation and applying the epoxy to these areas shall be in accordance with [Sec 704](#). The areas to be cleaned and epoxy sealed shall be as shown on the bridge plans.

3.0 Method of Measurement. The area to be cleaned and epoxy sealed will be computed to the nearest square foot (0.1 m²). Final measurement will not be made except for authorized changes during construction or if appreciable errors are found in the contract quantity.

4.0 Basis of Payment. Payment for the above described work, including all material, equipment, labor and any other incidental work necessary to complete this item, will be based on the contract plan quantities and will be considered completely covered by the contract unit price for "Clean and Epoxy Seal". Any change in the contract plan quantities, based on approved change orders, will be paid for at the contract unit price.

JOB SPECIAL PROVISIONS (BRIDGE)

F. SURFACE SEALING CONCRETE

1.0 Description. This provision allows surface sealing concrete to be applied as last order of work.

2.0 Construction Requirements. The surface of the new concrete shall be surface sealed in accordance with [Sec 703.3.8](#) except that lanes may be opened to traffic after the concrete has properly cured in accordance with [Sec 703](#) and the sealant applied as a last order of work. Any lanes open to traffic prior to surface sealing shall have foreign materials removed. Surfaces that are sealed after each stage of construction shall have all vertical construction joints between stages protected from the surface sealant. If asphalt roadway surface is adjacent to the new concrete, the asphalt surface shall be protected from spillage of the sealant.

3.0 Method of Measurement. No measurement will be made.

4.0 Basis of Payment. Payment for the above described work will be considered completely covered by the contract unit price for other items included in the contract.

G. REMOVAL OF CATHODIC PROTECTION SYSTEM

1.0 Description. This work shall consist of disengaging the power to the cathodic protection system during rehabilitation. The removal of the cathodic protection system shall include all of the cathodic protection system except as shown on the plans and noted herein.

2.0 Removal Requirements. Any damage cause by the contractor's operations to the cathodic protection system that is to remain in place, shall be repaired or replaced at the contractor's expense.

2.1 The existing cathodic protection system shall be turned off as directed by the engineer prior to beginning work. The existing cathodic protection system shall not be reused except as shown on the plans. All insulated wiring associated with the removal of the cathodic protection system shall be disposed by the contractor and as approved by the engineer.

2.2 With the cathodic protection system wiring through the slab removed, the existing access holes in the slab shall be plugged with grout or special mortar.

2.3 After removal of existing concrete wearing surface plus 1/4 in. of the existing deck, any remaining existing cathodic protection system in the longitudinal slots in the top of the deck that is securely embedded, may be left in place.

2.4 If during removal of the cathodic protection system, the existing concrete deck is damaged and not covered by new concrete, the areas on the deck shall be repaired with Class B-1 concrete in accordance with [Sec 704](#). If the concrete is damaged at other locations, the repair areas shall be made with a qualified special mortar. The qualified special mortar shall be in accordance with [Sec 704](#).

3.0 Method of Measurement. No measurement will be made.

4.0 Basis of Payment. Payment for the above described work, including all material, equipment, labor and any other incidental work necessary to complete this item, will be

JOB SPECIAL PROVISIONS (BRIDGE)

considered completely covered by the contract lump sum price for "Removal of Cathodic Protection System".

H. SURFACE SEALING LOW SLUMP CONCRETE

1.0 Description. This provision allows surface sealing low slump concrete to be applied as last order of work.

2.0 Construction Requirements. The surface of the low slump concrete shall be surface sealed in accordance with [Sec 703.3.8](#) except that lanes may be opened to traffic after the low slump concrete has properly cured in accordance with [Sec 505](#) and the sealant applied as a last order of work. Any lanes open to traffic prior to surface sealing shall have foreign materials removed. Surfaces that are sealed after each stage of construction shall have all vertical construction joints between stages protected from the surface sealant. If asphalt roadway surface is adjacent to the new low slump concrete, the asphalt surface shall be protected from spillage of the sealant.

3.0 Method of Measurement. No measurement will be made.

4.0 Basis of Payment. Payment for the above describe work will be considered completely covered by the contract unit price for other items included in the contract.

I. REMOVAL OF EXISTING BEARINGS

1.0 Description.

1.1 This work shall consist of but is not limited to raising and supporting existing girders, removing and disposing of the existing bearings and anchor bolts as noted on the plans and performing all other required preparations prior to installing new bearings and anchor bolts as shown on plans.

1.2 The responsibility for the design and construction of falsework required to support the girders during bearing removal, and new bearing installation shall rest solely with the contractor. The falsework shall be capable of supporting all applicable dead loads, any contributed live load including impact from any construction loads with an adequate factor of safety provided.

1.3 Existing bearing top plates shall be removed and girders surfaces cleaned and coated before placement of new bearing extension and sole plates. The removal of the existing bearing top plate and cleaning shall be completed in such a manner as to not cause any damage to the existing bottom flange. Method of removal will be reviewed by the engineer.

1.4 The new bearings shall be installed and the falsework removed before any new slab concrete is poured.

2.0 Construction Requirements and Materials.

2.1 Raising and Supporting the Superstructure.

2.1.1 The contractor shall exercise caution when supporting the structural steel and shall raise the girders the minimum extent necessary to perform this work and a maximum of 1/4 inch.

JOB SPECIAL PROVISIONS (BRIDGE)

2.1.2 Temporary timber supports (bearing stiffeners) shall be placed between girder flanges at each jacking location.

2.1.3 With the concrete deck removed, raising the girders shall be done simultaneously and shall be done to prevent damage to the adjoining steel.

2.1.4 Before commencing operations, the contractor shall provide the method and sequence of operation proposed to be used which shall include the complete working plans for the temporary falsework for supporting the girders. The lifting operation shall be done only when authorized, but such authorization shall not relieve the contractor of responsibility for the safety of the operation or for damage to the structure.

2.2 Bearing Removal.

2.2.1 After the structural members are supported, the contractor shall remove the existing bearings.

2.2.2 The contractor shall remove the existing anchor bolts to the extent required for the installation of new anchor bolts as required by the bridge plans and as authorized by the engineer.

2.3 Cleaning and Painting. Bottom surface of existing flange which will become faying surfaces of new connections shall be cleaned and painted with one coat of Gray Epoxy-Mastic Primer (non-aluminum).

3.0 Method of Measurement. Final measurement for removing existing bearings and anchor bolts (as noted on plans) and preparation for the installation of the new bearings and anchor bolts will be made per each.

4.0 Basis of Payment. Payment for furnishing and placing all temporary falsework, materials, removals, disposal of all falsework, labor, tools, equipment and all incidentals necessary to complete this item will be considered completely covered by the contract unit price for "Removal of Existing Bearings".

J. EPOXY PRESSURE INJECTING

1.0 Description. Shear crack as on the plans shall be pressure injected with epoxy. The engineer will designate the cracks to be repaired.

2.0 Material.

2.1 Epoxy. The epoxy material shall consist of a two-component system in accordance with the requirements of ASTM C 881, Type IV, Grade 1, except that the viscosity shall be a maximum of 4.5 poise (0.45 Pa·s). The Class designation of the epoxy shall be determined according to the temperature that exists on the job.

2.2 Certification. The contractor shall furnish manufacturer's certification that the material supplied is in accordance with these specifications. The certification shall include or have attached typical test results for all specified properties required by ASTM C 881 for the injecting resin. The engineer reserves the right to sample and test any or all material supplied.

JOB SPECIAL PROVISIONS (BRIDGE)

3.0 Construction Requirements. The surface to receive the epoxy grout shall be cleaned of laitance, grease and foreign matter by sandblasting. The cracks shall be cleaned of debris by using oil-free and water-free compressed air or vacuum. After the cracks are cleaned, the epoxy shall be injected in accordance with manufacturer's recommendations. The temporary surface seal and placement and method of attachment of injection ports shall be in accordance with the epoxy manufacturer's recommendations.

4.0 Method of Measurement. The extent of epoxy pressure injecting may vary from the estimated quantity but the contract unit price shall prevail regardless of the variation. The epoxy pressure injecting will be measured to the nearest linear foot (0.5 m).

5.0 Basis of Payment. Accepted quantity of epoxy pressure injecting will be paid for at the contract unit price. Payment for the above described work, including all material, equipment, labor and any other incidental work necessary to complete this item, will be considered completely covered by the contract unit price for "Epoxy Pressure Injecting".

K. CLEANING AND COATING EXISTING BEARINGS

1.0 Description. This work shall consist of cleaning and coating existing bearings as specified on the plans and as directed by the engineer.

2.0 Construction Requirements.

2.1 Cleaning and Coating. Bearings shall be cleaned and coated in accordance [Sec 1081](#). Coating of bearings shall be as indicated for coating existing steel as specified in the contract documents.

3.0 Method of Measurement. Measurement for cleaning and coating existing bearings will be made per each.

4.0 Basis of Payment. Payment for the above described work, including all material, equipment, labor and any other incidental work necessary to complete this item, will be considered completely covered by the contract unit price for "Cleaning and Coating Existing Bearings".

L. CURING CONCRETE ADJACENT TO EXPANSION DEVICE

1.0 Description. This special provision covers construction requirements for curing concrete adjacent to the expansion device.

2.0 Construction Requirements.

2.1 Type III cement may be used to accelerate the set of the concrete. Accelerating additives containing chlorides will not be permitted.

2.2 Following texturing, fresh concrete shall be sprayed immediately with a curing compound in accordance with [Sec 703](#).

2.3 The concrete surface shall be covered with clean curing mats as soon as the curing compound has dried sufficiently to prevent adhesion and the concrete surface will support the

JOB SPECIAL PROVISIONS (BRIDGE)

curing mat without marring or distorting the finish, but not more than 90 minutes after the concrete is textured. The mats shall be sufficiently wet at the time of placement to prevent moisture absorption from the finished surface. The curing mats shall be kept continuously wet for minimum of 4 hours following the concrete placement. The contractor shall control the water runoff so as not to cause a traffic hazard.

2.4 The continuous wet cure shall be maintained a minimum of 4 hours and until the concrete has attained a minimum compressive strength of 3,200 psi (22 MPa). The contractor shall not reopen the structure to any public vehicular traffic until the concrete has attained a compressive strength of 3,200 psi. Plates shall not be placed over each repair area or joint being repaired during the concrete curing time.

3.0 Basis of Payment. No direct payment will be made for curing the concrete as specified by this special provision.